

The Playground, Shade and Surfacing Depot, LLC

Proposal



200 N. Rufe Snow Drive, Suite 209

Keller, TX 76248

(817) 585-4636

sales@playgroundshadeandsurfacing.com

INVOICE NO.

DATE July 13, 2017

CUSTOMER ID

EXPIRATION DATE

BILL TO: The Rise School of Dallas - Moody Family YMCA

Attn: Maude Pampel, M.S.

6000 Preston Road

Dallas, TX 75205

Office: (214) 373-7473

Cell:

Email: mpampel@ymcadallas.org

SHIP TO:

(If Different)

TEAM MEMBER	JOB	PAYMENT TERMS	DUE DATE
Shane Jefferys	Shade Structure	TBD	

QUANTITY	DESCRIPTION	UNIT PRICE	LINE TOTAL
1.00	Two Playground Shades to include the following:	\$	
	(1) 23' x 15' x 8' Entry Hip & Ridge Rectangular Shade with 4 embedded columns. Preliminary Engineering calls for 5" Columns & 2.875" rafters. See concept rendering. TODDLER AREA		
	(1) 32' x 25' x 10' Entry Hip & Ridge Rectangular Shade with 4 embedded columns. Preliminary Engineering calls for 6" Columns & 3.5" rafters. See concept rendering. 2-5 PLAY AREA		
	Includes standard installation through soil of columns disposing of footer spoils onsite or in customer provided dumpster. Price assumes good access & excludes excavation of any rock, concrete or other materials below grade. Assumes engineering approves for parking garage install.		
	Price includes Z-Coat Finish: the most comprehensive steel finishing process in the industry.		
	Price includes Patented Glide Elbow System to allow for easier removal/re-install of shade fabric in cases of severe inclement weather or snow.		
	NOTE: Customer to have any irrigation system turned off prior to install & any irrigation capping or redirection is responsibility of customer. Repair of landscaping and/or sod after construction is the responsibility of the Customer. Must be able to access w/ Bobcat equipment.		
	Playground roof may need to be removed for shade clearance to keep entry height lower.		
	OPTIONAL ITEMS:		
2.00	•Engineered Stamped/Sealed Drawings if needed for Permitting: \$650	\$	
	•Offsite disposal of footer spoils: \$950		
	10 Year Limited Pro-Rated Warranty on Fabric and 20 Year Limited Warranty on Frame from Mfg. Standard specifications engineered to withstand hurricane force 1 wind gust 93mph w/ fabric installed; up to 150 mph winds with fabric removed. Meets ASTM guidelines. Shade fabric should be removed in cases of heavy snow, ice or severe inclement weather. Detailed warranty available on request or at purchase.		
	Excludes sales tax which if required will be added		
	Excludes permitting or fees which may be required		

To accept this proposal, sign here and return with payment:

Date: _____

SUBTOTAL \$

FREIGHT ESTIMATE*

8.25%SALES TAX (if applicable)

TOTAL \$

This quotation is subject to policies and the following terms and conditions. Our quotation is based on shipment of all items at one time to a single destination, unless noted, and changes are subject to price adjustment. Any approved returns subject to a 30% restocking fee. Credit Cards subject to a 3.75% fee

Pricing: F.O.B. factory, firm for 30 days from date of quotation

Shipment: Order shall ship within 30-45 days after receipt and acceptance of your order, color selections, approved submittals and receipt of payment.

***Freight charges:** We make every effort to provide accurate freight prices, however, these are estimates and add'l charges may apply.

Taxes: State and local taxes, if applicable, will be added at time of invoicing unless a tax exempt certificate is provided at the time of order entry.

Receipt of goods if Self-Install: Customer shall receive, unload and inspect goods upon arrival, noting any discrepancies on the Delivery Receipt prior to written acceptance of the shipment. **Driver WILL NOT unload trailer and a fork lift may be needed to unload equipment depending on size of order.**

Exclusions: Unless specifically included, this quotation excludes all site work and landscaping; removal of existing equipment; acceptance of equipment and off-loading; storage of goods prior to installation; equipment assembly and installation; safety surfacing; borders and drainage provisions.

Customer is responsible for all permits should they be required. Customer will be financially responsible for additional cost for Engineer Stamped Drawings if required for permitting. Customer responsible for proper drainage of site.

Installation: Shall be by a Certified Installer. Customer shall be responsible for scheduling coordination and site preparation. Pricing assumes level grade less than 2% slope & allow installation equipment access min. 7'W. Purchaser shall be responsible for additional costs to repair, replace or relocate unknown conditions such as buried utilities, tree stumps, bedrock, lines such as irrigation, drainage, sewer or other slow moving utilities or any concealed materials or conditions that may result in additional labor or material costs. Unless otherwise noted, footer spoils spread onsite. Repair of landscaping and/or sod after construction is the responsibility of the Customer. Customer to have any irrigation system turned off prior to install & any irrigation capping or redirection is responsibility of customer. For shade & shelter, footing designs based on 1500PSF soil bearing pressure.

Acceptance of this proposal indicates your agreement to the terms and conditions stated herein.

THANK YOU FOR THE OPPORTUNITY TO EARN YOUR BUSINESS!